

Construction work information

Time: 7 a.m.-19 p.m.

Access: Via Route des Romelles

Measures to limit disturbance:

- Early morning arrival of transport trucks to avoid congestion on the main road
- Monitoring of machines on the construction site to avoid air and noise pollution
- Asphalt surface coating to avoid mud on construction site roads
- Wheel cleaner available when the machines finish the earthworks
- Use of drip trays (in case of jerry can leakage). Absorption trays (self-service) in case of leakage from equipment
- Use of double-walled storage tanks
- Daily sweeping of the construction site
- Installation of a construction site pump to discharge and drain the water from the structure. Night watchman surveillance
- Treatment of pumping water with CO2 neutraliser before it is discharged into the network
- Use of drilling rather than boring for excavation support systems
- Acoustic partitioning of the concrete mixing plant and shock-absorber system to avoid structure-borne noise
- Monitoring of acoustic disturbance threshold. Smartphone alert if threshold is exceeded and intervention by the Department of Territory (DT)
- Ban on use of radios on the site

Direction of truck traffic around the construction site:

Use of public roads outside and inside the construction site. Traffic management by a site manager in accordance with the progress of the construction site, including the housing site.